

WDC Transportation Update

April 2023

WESTLAND
District Council | Te Kahui o Poutini



Update Topics Covered



1. Transportation Survey Results
2. Walkshop findings (Dr Rodney Tolley)
3. Parking Strategy Update
4. Completed Works
5. Works Underway
6. Upcoming Works
7. Recent/Ongoing Challenges – Asset Retreat

2023 Dr Rodney Tolley Walkshop

General Feedback & Observations from Dr Tolley

- 30km/h CBD area is excellent
- Revitalised areas (Revell Street) could benefit from shade plantings
- Good to see more businesses interested in outdoor seating/dining/parklets
- We could be doing more to encourage children to walk/ride to school
- Link to evening presentation available on WDC Website

Parking Strategy Progress Update

- Initial parking surveys have been carried out over the summer peak periods. Some findings are as follows:
- Trouble spots (greater than 85% occupancy)
 - Weld Street (52 Parks)
 - Tancred Street (100 Parks)
 - Sewell Street (47 Parks)
- Immediate CBD area has capacity for approximately 460 cars (on street parking only and average of approximately 67% occupancy)
- 2 Carpark areas with a capacity of a further 50 vehicles currently reach 20-30% occupancy
- Periphery of the CBD (Gibson Quay, Beach Street) has capacity for a further 150+ carparks with occupancy in these areas sitting at approximately 30%

Parking Strategy Progress Update

Observations : Shopkeepers parking all day in front of their own business.
Abundance of vacant carparks around the edges of town.
Poor wayfinding for carparking.
Campervans and Bus Parking could be moved to the periphery.

Next steps : Parking survey for public feedback to be carried out after June.

Completed Works

- 2022/23 Reseal Works now completed
18.6km reseals completed
- Annual Pavement Remark
- Cauldron Creek Bridge Replacement
- Davie Street Rip and Remake (Park to Hampden)

Works Underway

- **West Coast Councils Bridge & Structure Asset Management Contract**
Progressing with bridge inspection programs and Data updating
- **West Coast Councils Regional Asset Management Services Contract**
Road Asset Management systems database merge project underway
Maintenance cost data collection proceeding
Preparation for Fair Value Assessments on Transportation Assets underway.
- **Haast Jackson Bay Resilience improvements**
Design scoping has been carried out and now proceeding to the Consent application stage.
- **Haast Jackson Bay Pavement Rehabilitation**
Westroads have started this project and are making excellent progress with much of the foundation work nearing completion.
- **Footpath Mtce/Renewals**
Project underway and progressing.

Works Underway

- Footpath Mtce/Renewals

Project underway and progressing.

Location	Street Name	Side	Start	End	Width (m)	Length (m)	Note	Column1
Hokitika	Hall Street	Left	478	688	1.1	60	Grinding and grout repair	Completed
Hokitika	Park St	Left	1281	1378	1.5	97	Grout ,grind repair	Completed
Hokitika	Tancred Street	Left	50	50	2.7	0	Replace Pram crossing	Completed
Hokitika	Rolleston St	Right	823	1054	1.2	135	grind repair and grouting	Completed
Hokitika	91 Hall St	Left	168	168	1	0	Install grate crossing	Completed
Hokitika	Bealey Street	Right	980	986	1.5	50	Replace broken slab -mainly due to water entering through gaps (RP.957-.990),(RP.995-1.002),(RP1.010-1.015)+ some extra bits @ the starting	Completed
Hokitika	Bealey Street	Right	980	986	1.5	6	Replace broken slab (1.036-1.040)+ adjacent driveway	Completed

Works Underway

Location	Street Name	Side	Start	End	Width (m)	Length (m)	Note	Column1
							Mill & chipseal (RP0.015-0.022) Patch repairs 10m2(RP 0.022-.058)	Work in Progress - waiting for chipseal
Hokitika	Revell Street	Left	14	127	2.3	113	Mill & Chipseal(RP0.058-0.098)	
Hokitika	Jollie St	Left	170	352	1.3	182	Repairs(1604.15)+Moss Removal(1419.6)	Work in Progress
Hokitika	Jollie St	Right	170	352	1.3	182	Repairs(1604.15)+Moss Removal(1419.6)	Work in Progress
Hokitika	Sewell St	Both	553	553		0	Install Tactile Pads at pedestrian crossing	Work in Progress

Works Underway

Location	Street Name	Side	Start	End	Width (m)	Length (m)	Note	Column1
Haast	Marks Road	Right	299	471	1	172	base estimate only-check width	Programmed for June
Hokitika	Hoffman Street	Left	600	805	1.2	205	Repair Works+sunken footpath+moss removal+Kerb and channel need to be replaced at few place	Programmed for May
Hokitika	Hoffman Street	Right	600	805	1.4	205	Repair works+Moss removal	Programmed for May
Kaniere	Kaniere Road	Left	3570	3793	1.2	223	Renewal	Programmed for May
Kaniere	Kaniere Road	Left	3421	3543	1.2	122	Reseal	Programmed for May
Ross	State highway	Left	579	687	2.5	108	Reseal	Programmed for May
Ross	State Highway 6 (Ross)	Right	941	1160	2.5	219	Renewal	Programmed for May
Ross	State highway	Left	460	565	2.5	105	R&M - Moss and Mould treat and removal	Programmed for May
Ross	Aylmer Street	Right	5	151	2.5	146	reseal -except the concrete portion in front of hotel	Programmed for May
Ross	Aylmer Street	Right	5	151	2.5	146	Hotel Front+Driveway before the hotel	Programmed for May
Ross	Aylmer Street	Right	158	221	2	63	moss and mould treat and removal +patch repairs(7m2)	Programmed for May
Ross	Sale Street	Right	242	312	2	70	R&M - Moss and Mould treat and removal	Programmed for May
Ross	Sale Street	Left	242	312	2	70	R&M - Moss and Mould treat and removal	Programmed for May
Ross	Gow Street	Left	10	103	3	93	R&M - Moss and Mould treat and removal	Programmed for May
Ross	Gibson Street	Right	242	343	2	101	R&M - Moss and Mould treat and removal	Programmed for May
Ross	Gibson Street	Left	242	368	2.6	126	R&M - Moss and Mould treat and removal	Programmed for May
Ross	State Highway 6 (Ross)	Right	98	339	1	241	R&M - Moss and Mould treat and removal	Programmed for May
Ross	State Highway 6 (Ross)	Left	98	323	1	225	R&M - Moss and Mould treat and removal	Programmed for May
Whataroa	Wilson Street	Right	8	116	1	108	Moss and mould removal	Programmed for May
Whataroa	Murray Street	Left	5	213	1	208	Moss and mould removal	Programmed for May
Whataroa	Robert Street	Left	8	113	1	105	Moss and mould removal	Programmed for May
Kumara	Fifth St	Right	8	214	2	206	Patch Work-right side+Moss removal	Programmed for June
Kumara	State Highway 73 (Kumara)	Left	845	956	1.9	111	Renewal(width is not 1.9m throughout)	Programmed for June

Upcoming Works

- Fox Creek Culvert repair works – Working with Mtce contractor to identify affordable options for repair. Work now targetted for 2023/24 fiscal year.
- Speed limits around schools (Combined project with Grey & Buller Councils) – Still in preliminary stages with Delivery set for 2023/24 fiscal year
- 2023/2024 Reseal programme (initial site identification & investigation)
- Waitaha Valley Road Improvements – Isolated widening/passing bays.

Recent/Ongoing Challenges

- Allen Road Washout (April Weather Event)



Recent/Ongoing Challenges

- Totara Valley Road Slip (April Weather Event)



Recent/Ongoing Challenges

- Forks-Okarito Road Washout (February 2023 Weather Event)



Recent/Ongoing Challenges

- Milltown Road Culvert Washout



Asset Retreat

- Other Councils are already considering this proposition
- While it is good to keep all formed roads open there comes a time when some roads just aren't economic to keep fixing/maintaining
- WDC has already gone past that point for some parts of the network
- Need to have open conversation between Council and Public/Road users to develop and agree on an Asset Retreat Strategy.



Questions?